BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHDULE-B

Name of Work: Providing UGD connection to SC/ST houses at Papamma Compound at Kammagondanahalli in Shettyhalli Sub-Division, Ward No-12, Under 22.75% grant

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Earth work exacavation of foundation trenches for culverts in hard soil not exceeding 2m in depth including dressing the bottom and sides of trenches stacking and excavated soil clear from edges of excavation and subsequent filling around hume pipes / masonry is 15 cms. layers with compaction including disposal of surplus soil as directed with a lead of 30m cost of labour complete as per specifications.	Cum	582.28	163.24	Rupees One Hundred Sixty Three and Twenty Four Paise Only
2	Providing and laying in position to required level or slope 300mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per specifications.	Mt	570.00	570.28	Rupees Five Hundred Seventy and Twenty Eight Paise Only
3	Constructing brick masonry circular type manhole 0.91 m internal dia at bottom 0.91m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement foundation concrete 1:3:6 mix using 40mm and downsize granite metal and making necessary channel in cement concrete 1:2:4 mix with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty , HD-20 grade designation) 560mm internal diameter confirming IS:12592, total weight cover and frame to be not less than 182kg fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of machineries complete as per specifications.	Nos	40.00	8869.02	Rupees Eight Thousand Eight Hundred Sixty Nine and Two Paise Only
4	Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Cum	22.44	3824.48	Rupees Three Thousand Eight Hundred Twenty Four and Forty Eight Paise Only
5	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	175.50	140.98	Rupees One Hundred Forty and Ninety Eight Paise Only

Technical Manager-2
Signature of the Contractor
KRIDL, BBMP, Bangalore

Executive Engineer

6	P. .viding & Fixing SFRC Cover and fram (ID) Heavy Duty Material complete as per specifications.	Nos	50.00	954.00	Rupees Nine Hundred Fifty Four Only
7	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m including cost of all labour complete as specifications.	Cum	335.16	43.88	Rupees Forty Three and Eighty Eight Paise Only
8	Conveying the excavaed earth to a distance of 2kms with all lead & lifts including loading & unloading charges etc., complete as per specifications.	Cum	582.28	71.34	Rupees Seventy One and Thirty Three Paise Only

Technical Manager-2
KRIDL, BBMP, Bangalore
Signature of the Contractor

Executive Engineer,
Dasarahalli Division,